

CONCRETE

CONCRETE POWER TROWELS, WALK-BEHIND AND RIDE-ON (24 - 46 IN, TWIN ROTOR)

FACTORY DIRECT LANDED IN RAND

R11 611 – R75 953

6 options, priced in the table below · Landed and cleared, collected from our Johannesburg warehouse.

Power trowels (helicopters) that float and finish fresh concrete slabs to a smooth, hard surface: warehouse floors, slabs, garages and parking decks. Walk-behind models from 24 to 46 inches, and twin-rotor ride-on machines that finish large floors fast. Honda petrol engines.

LEAD TIME About 10-12 weeks: 15-20 working days to build, then sea freight (35-45 days) and clearing

SPECIFICATION

WHAT YOU ARE GETTING

Walk-behind	24, 30, 36 and 46 in (60 - 120 cm working diameter), 4 blades, 0 - 130 rpm	
Ride-on	Twin rotor 2 × 80 cm (FMG-S30) or 2 × 100 cm (FMG-S36, 75 in working width), 8 blades	
Engines	Honda GX160 5.5 hp, GX270 9 hp, GX390 13 hp or GX690 24 hp petrol	
Warranty	One year from the manufacturer	
Options	6 models below	
FMG-24 walk-behind, 60 cm, Honda GX160		R11,611
FMG-30 walk-behind, 80 cm, Honda GX160		R15,378
FMG-36 walk-behind, 100 cm, Honda GX160		R15,788
FMG-46 walk-behind, 120 cm, Honda GX270		R25,731
FMG-S30 ride-on twin rotor, 2 × 80 cm, Honda GX390		R52,135
FMG-S36 ride-on twin rotor, 2 × 100 cm, Honda GX690		R75,953
Lead time	About 10-12 weeks: 15-20 working days to build, then sea freight (35-45 days) and clearing	

Specifications are as supplied by the manufacturer and confirmed at inspection before shipping. Tell us the job and we will confirm this is the right machine for it, or say if it is not.

Prices are landed and cleared in South Africa: freight, duty and clearing included. Buy online through Payfast, or pay by EFT into our company account against a written quotation.

Tryg Enterprises (Pty) Ltd · Reg. 2026/621598/07 · 7 Wagen Road, Estcourt, KwaZulu-Natal, 3310 · sales@tryg.co.za · +27 68 940 7376