

EARTHMOVING

MINI EXCAVATOR, 6 T, YANMAR DIESEL, CAB WITH AIR CONDITIONING (FWJ-6000)

FACTORY DIRECT · LANDED IN RAND

R764 243

Landed and cleared, collected from our Johannesburg warehouse.

A 6-tonne crawler excavator for trenching, foundations, plant hire and farm work: a Yanmar 4TNV94L diesel (36.2 kW), a closed cab with air conditioning and steel tracks. Digs 3.86 m deep and reaches 6.17 m.

LEAD TIME — About 10-12 weeks: 15-20 working days to build, then sea freight (35-45 days) and clearing

SPECIFICATION

WHAT YOU ARE GETTING

Operating weight		6,000 kg
Engine	Yanmar 4TNV94L diesel, 36.2 kW	
Bucket	0.22 m³	
Max digging depth		3,860 mm
Max digging height		5,750 mm
Max digging reach		6,170 mm
Undercarriage	Steel tracks, 400 mm shoes, 2,000 mm on the ground, 1,960 mm track width	
Cab	Closed cab with air conditioning	
Warranty	One year from the manufacturer	
Options	1 model below	
FWJ-6000, 6 t, Yanmar diesel, cab with A/C, steel tracks		R764,243
Lead time	About 10-12 weeks: 15-20 working days to build, then sea freight (35-45 days) and clearing	

Specifications are as supplied by the manufacturer and confirmed at inspection before shipping. Tell us the job and we will confirm this is the right machine for it, or say if it is not.

Spec sheet: Mini excavator, 6 t, Yanmar diesel, cab with air conditioning (FWJ-6000) · https://www.tryg.co.za/products/mini-and-midi-excavators

Prices are landed and cleared in South Africa: freight, duty and clearing included. Buy online through Payfast, or pay by EFT into our company account against a written quotation.