

COMPACTION

PLATE COMPACTORS AND TAMPING RAMMERS (54 - 175 KG)

FACTORY DIRECT | LANDED IN RAND

R8 519 – R21 924

6 options, priced in the table below · Landed and cleared, collected from our Johannesburg warehouse.

Petrol plate compactors for paving, interlocking bricks, driveways and sub-base, and jumping-jack rammers for trenches, foundations and backfill where a plate can't reach. Honda and Loncin engines, one-way or reversible plates.

LEAD TIME About 10-12 weeks: 15-20 working days to build, then sea freight (35-45 days) and clearing

SPECIFICATION

WHAT YOU ARE GETTING

Plate compactors	FPB-15: 510 × 490 mm plate, 15 kN; FPB-20: 430 × 550 mm, 20 kN, 70 Hz; FPB-S30G: 500 × 690 mm, 30 kN, reversible
Rammers	Jump 45 - 80 mm, 300 - 700 blows a minute, 275 × 330 mm foot (FYCH-80 / 80G)
Engines	Loncin 196 cc 6.5 hp, Honda GX160 5.5 hp or Honda GX270 9 hp petrol
Warranty	One year from the manufacturer
Options	6 models below
FPB-15 plate compactor, 54 kg, Loncin 6.5 hp	R8,519
FYCH-75B rammer, 75 kg, Loncin 6.5 hp	R9,572
FPB-20 plate compactor, 85 kg, Honda GX160	R12,324
FYCH-80 rammer, 82 kg, Honda GX160	R13,569
FYCH-80G rammer, 80 kg, Honda GX160, 60 - 80 mm jump	R14,023
FPB-S30G reversible plate compactor, 175 kg, Honda GX270	R21,924
Lead time	About 10-12 weeks: 15-20 working days to build, then sea freight (35-45 days) and clearing

Specifications are as supplied by the manufacturer and confirmed at inspection before shipping. Tell us the job and we will confirm this is the right machine for it, or say if it is not.

Prices are landed and cleared in South Africa: freight, duty and clearing included. Buy online through Payfast, or pay by EFT into our company account against a written quotation.

Tryg Enterprises (Pty) Ltd · Reg. 2026/621598/07 · 7 Wagen Road, Estcourt, KwaZulu-Natal, 3310 · sales@tryg.co.za · +27 68 940 7376